**ALTERATIONS AND ADDITION** to
the former Jennings County Carnegie Library for the new
**CITY HALL** for North Vernon, Indiana

ISSUED: February 6, 2012

BY: KZF Design
700 Broadway Street
Cincinnati, Ohio 45202
(513) 621-6211
FAX (513) 621-6530

This Addendum forms a part of the Contract Documents and modifies previously issued specifications and drawings. Bidders shall update their Bidding Documents with the information contained in this Addendum. Where new Drawings are enclosed with this Addendum, discard the old Drawing and insert the new. Where Supplemental Drawings are enclosed with this Addendum, attach the Supplemental Drawing to the documents as noted. Where only written modifications are given, copy the information onto the appropriate Documents and note the Addendum number.

## 1. BIDDER QUESTIONS

1. Bidder Question: To what degree does the condition of the concrete floor in the basement VCT areas need to be. Skimmed & cracks filled, or the entire areas gone over with self leveling material. My floor mechanic says that just skimming & filling the cracks will cause tile failure within a few months. The self leveler will just add a substantial cost to the basement, and after all we are trying to keep costs down. Is there any possibility that the office & break room can also be finished with the carpet tiles?

   KZF Response: We need to do what is the least expensive and still work. Change floor finishes as follows:

   Room 101 large office from VCT to Carpet Tiles
   Room 104 break room from VCT to Carpet Tiles

2. Bidder Question: Is domestic steel required?

   KZF Response: There are not requirements for domestic steel.

3. Bidder Question: Can cast iron be used for vent piping in lieu of copper?

   KZF Response: Yes cast iron vent piping is permitted.

4. Bidder Question: Are the muntins at the front door and side lites required to be true divided lites?

   KZF Response: No. Applied muntins on the exterior are acceptable.

**2. DRAWINGS**

The following drawings have been revised and are hereby reissued. Changes are relatively minor and are summarized as follows:

AD01 - First Floor Demolition Plan - Selective demolition is indicated at existing partitions believed to be load bearing. This occurs in the area east of the existing communicating stair. Note 19 has been added.

A102 - Second Floor Plan - A control joint was added to the brick veneer in the addition. This is located opposite the elevator.

A202 - Exterior Elevations - A control joint was added to the brick veneer in the addition. Note 6 on Elevation 02 has been added.

A501 - Partition Types Miscellaneous Details: Detail 07 exterior handrail was revised.

A502 - Miscellaneous Details: Window details 02 and 03 were revised. Lintles, flashing and weeps were clarified.

END OF ADDENDUM